



NOTES:

- 1. DRILLED CORNERS SHALL BE 2" DIAMETER HOLES DRILLED TO THE DEPTH OF SAWCUT. AFTER INSTALLATION OF LOOP WIRE, FILL SAWCUT WITH SEALANT.
- 2. CONTRACTOR HAS THE OPTION TO USE DETAIL "B" FOR 90° DRILLED CORNERS IN PLACE OF 45° CUT CORNERS.

| INDUCTION LOOP DETECTOR (6' x 20') | | REVISION & DATE |
|------------------------------------|---|-------------------|
| ARLINGTON VIRGINIA | ARLINGTON COUNTY, VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES | DRAWING NO. 78-02 |