


## NOTES

1. NOTIFY THE DPR URBAN FORESTER AT LEAST 72 HOURS IN ADVANCE OF THE SCHEDULED INSTALLATION OF TREE PITS AND PLANTING OF ANY STREET TREES FOR INSPECTION. CONTACT [URBANFORESTRY@ARLINGTONVA.US](mailto:URBANFORESTRY@ARLINGTONVA.US) IF URBAN FORESTER IS NOT KNOWN.
2. PLANT TREES ACCORDING TO THE APPROVED PLANS. DEVIATIONS MUST BE REVIEWED AND APPROVED BY THE URBAN FORESTER.
3. TREES SHALL BE NURSERY GROWN SPECIMENS THAT MEET THE LATEST EDITION OF THE AMERICAN STANDARDS FOR NURSERY STOCK (ANSI Z60).
4. CONTACT MISS UTILITY AT FOR UTILITY LOCATIONS PRIOR TO EXCAVATION.
5. AT TIME OF PLANTING PRUNE ONLY BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A MAJOR OBSTRUCTIONS TO PEDESTRIANS. DO NOT PRUNE INTO OLD WOOD ON EVERGREENS. CROSSING BRANCHES MAY BE DIRECTED TO BE PRUNED BY THE URBAN FORESTER.
6. TREE PIT AND TREE STRIP PLANTING AREA DIMENSIONS: SEE PLAN
7. PLANTING SOIL MIXTURE SHALL FOLLOW APPROVED PLAN REQUIREMENTS OR FOLLOW VIRGINIA TECH SOIL PROFILE REBUILDING SPECIFICATIONS, IF EXISTING SOIL IS ACCEPTABLE FOR USE.
8. IF THE QUANTITY OF ACCEPTABLE EXISTING SOIL IS INSUFFICIENT FOR THE PLANTING REQUIREMENTS, AND NOT OTHERWISE SPECIFIED IN THE PLAN, USE THE FOLLOWING SPECIFICATIONS. A SOIL TEST REPORT RESULTS FOR THE TOPSOIL WILL BE MADE AVAILABLE TO THE COUNTY URBAN FORESTER UPON REQUEST.
  - a. THE SOIL SHALL:
    - i. BE A USDA LOAM CONSISTING OF AT LEAST 15% BUT NOT MORE THAN 25% CLAY, AT LEAST 45% BUT NOT MORE THAN 70% SAND, , AND LESS THAN 55% CLAY AND SILT COMBINED, UNLESS OTHERWISE SPECIFIED IN THE PLANS.
    - ii. CONTAIN 2.0-5.0% ORGANIC MATTER
    - iii. HAVE SOLUBLE SALTS (SALINITY) NOT EXCEEDING 2.0 MMHOS/CM
    - iv. HAVE A SOIL PH BETWEEN 5.5 TO 7
    - v. BE FREE OF FOREIGN MATERIAL AND OTHER DEBRIS OVER 1 INCH IN LENGTH.
    - vi. BE FREE OF HEAVY METALS AND OTHER DELETERIOUS CONTAMINANTS.
    - vii. HAVE A NUTRIENT PROFILE SUFFICIENT FOR THE PLANTS SPECIFIED.
    - viii. BE FREE OF NOXIOUS WEEDS
9. TREES PLANTED WITHOUT THE TRUNK FLARE VISIBLE MAY BE REJECTED.
10. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER. REFER TO ARLINGTON COUNTY STANDARD STAKING DETAILS.
11. MULCH SHALL BE CLEAN, SCREENED, HARDWOOD BARK MULCH, PINE BARK MULCH, OR WOOD CHIPS, UNIFORM IN SIZE AND FREE OF STONES, CLOUDS, NON-ORGANIC DEBRIS AND OTHER FOREIGN MATERIAL.
12. ALL PLANTS SHALL BE WATERED TWICE: AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION. EACH WATERING WILL CONSIST OF 20 GALLONS PER TREE.



## GENERAL NOTES FOR STREET TREE PLANTINGS

FOR TREES PLANTED IN RIGHT-OF-WAY  
329300.5 (2026)

