DRAFT

Geotechnical Engineering Report

Lubber Run Recreation Center Arlington, Virginia

June 23, 2017

Terracon Project No. EW175052



Prepared for:

Bowman Consulting Group Chantilly, Virginia 20151

Prepared by:

Terracon Consultants, Inc.
Dulles, Virginia

Offices Nationwide Employee-Owned Established in 1965 terracon.com





June 23, 2017



Bowman Consulting Group 3863 Centerview Drive, Suite 300 Chantilly, VA 20151

Attn: Mr. Scott Delgado

Re: Geotechnical Engineering Report

Lubber Run Recreation Center

Arlington, Virginia

Terracon Project Number: EW175052

Dear Mr. Delgado,

Terracon Consultants, Inc. (Terracon) has performed geotechnical engineering services for the Lubber Run Recreation Center project. These services were conducted in accordance with Terracon's proposal PEW175052 dated May 25, 2017.

The report presents he findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations, paved parking areas, retaining walls, foundation walls and bioretention facilities for the proposed project.

We appreciate the opportunity to be of service to you on this project. Materials testing services are provided by Terracon. We would be pleased to discuss these services with you. Please contact us if you have any questions concerning this report, or if we may be of further service.

Sincerely,

Terracon Consultants, Inc.

Will Kelsey, E.I.T.

Senior Staff Engineer

Geotechnical Services

Muthu Arigovindan, P.E. LEED AP BD+C

Principal | Office Manage

Virginia 43793

Geotechnical Consulting & Testing, Inc., A Terracon Company 21505 Greenoak Way Dulles, VA 20166
P (703) 421 4000 F (571) 525 7001 terracon.com



TABLE OF CONTENTS

		Р	age
EXEC	IITIVE	SUMMARY	i
1.0	_	DUCTION	
2.0		ECT INFORMATION	
2.0		Project Description	
	2.2	Site Description	
3.0		JRFACE CONDITIONS	
3.0	3.1	Site Geology	
	3.2	Typical Subsurface Profile	
	J.2	3.2.1 Subsurface Conditions	
		3.2.2 Groundwater	
	3.3	Analytical	
	3.4	Infiltration Test Results	
4.0	_	ECHNICAL EVALUATION AND RECOMMENDATIONS	
7.0	4.1	Existing Fills	
	4.2	Suitability of On-site Soils	
	4.3	Excavation of On-Site Soils	
		4.3.1 Dewatering measures during Construction	
		4.3.2 Temporary excavations	
	4.4	Earthwork	
	•••	4.4.1 Proof-rolling	
		4.4.2 Structural Fill Material	
		4.4.3 Fill Placement and Testing	_
	4.5	Site Utilities	
	4.6	Foundation Support	
	4.7	Ground-supported Slabs	
	4.8	Seismic Site Classification	
	4.9	Foundation Walls, Backfill and Drainage	
	4.10	Retaining Wall Recommendations	
	4.11	Pavement Subgrade Preparation	
	4.12	Bio-Filter Facility	
5.0	CLOS	NG REMARKS	
	5.1	Additional Services	16
	5.2	GENERAL COMMENTS	16



APPENDIX A - FIELD EXPLORATION

Exhibit A-1 Site Location Plan
Exhibit A-2 Boring Location Plan

Exhibit A-3 Field Exploration Description

Exhibit A-4-1 through A-4-19 Boring Logs
Exhibit A-5 Site Photographs

APPENDIX B - LABORATORY TESTING

Exhibit B-1 Laboratory Testing

APPENDIX C - SUPPORTING DOCUMENTS

Exhibit C-1 General Notes

Exhibit C-2 Unified Soil Classification System



EXECUTIVE SUMMARY

A geotechnical exploration has been performed for the proposed community center to be constructed at 300 North Park Drive, Arlington, Virginia. Nineteen (19) borings, designated B-1 through B-19, and one (1) rock core were performed to depths ranging from 10 to 70 feet beneath existing ground surface. This report specifically addresses recommendations for the proposed community center, retaining walls, bio-filter and parking garage.

Based on the information obtained, the subsurface conditions at the site are suitable for the proposed construction. The following geotechnical considerations were identified:

- The proposed building may be supported on shallow footings bearing on the stiff to hard native soil, or newly placed structural fill.
- Assuming proper site preparation and any necessary subgrade repair, total and differential settlement should be within anticipated client/owner specifications.
- On-site native soils typically appear suitable for use as structural fill.
- The Seismic Site Class for the site is "C".
- Terracon should be retained during the site grading phase of the project to observe earthwork and to perform necessary tests and observations during subgrade preparation; proof-rolling; placement and compaction of controlled compacted fills; backfilling of excavations to the completed subgrade.
- Infiltration will be feasible at the proposed bio-filter location.

This summary should be used in conjunction with the entire report for design purposes. It should be recognized that details were not included or fully developed in this section, and the report must be read in its entirety for a comprehensive understanding of the items contained herein. The section titled **GENERAL COMMENTS** should be read for an understanding of the report limitations.

i



GEOTECHNICAL ENGINEERING REPORT LUBBER RUN RECREATION CENTER ARLINGTON, VIRGINIA

Terracon Project No. EW175052 June 23, 2017

1.0 INTRODUCTION

This report presents the results of our geotechnical engineering services performed for the proposed new construction of a recreation center located at 300 North Park Drive in Arlington, Virginia. Our geotechnical engineering scope of work for this project included:

- Advancing nineteen (19) soil test borings to planned depths ranging from 10 to 100 feet below existing site grades.
- Infiltration testing within the footprint of the planned bio-filter facility
- One (1) rock core to determine the quality of on-site rock.
- Test pits to determine the Seasonal High Water Table (SHWT)

The purpose of these services was to provide information and geotechnical engineering recommendations including, but not limited to:

subsurface soil conditions	•	pavement design and construction
earthwork	•	floor slab design and construction

groundwater conditions
 below grade wall design considerations

infiltration test results
 retaining wall design considerations

foundation design and construction seismic considerations

bio-filter design considerations

2.0 PROJECT INFORMATION

2.1 Project Description

Information provided by the client included the following documents:

- Boring Layout Building Height Diagram dated May 8, 2017 and provided by Bowman Consulting Group.
- LRR Schematic Site Plan dated April 25, 2017 and provided by Bowman Consulting Group.
- Exterior Views developed by VMDO and dated May 4, 2017.
- Scheme Current Plan developed by VMDO dated April 24, 2017





ITEM	DESCRIPTION							
Proposed construction	 Demolition of an existing 2 story structure One to three story recreation center with an approximately 40,000 sf footprint. The building will incorporate green roofs and below grade structures. Below-grade parking structure, at the issuance of this report, it has not been determined if the parking structure will be one story or two stories. Three retaining walls with maximum heights of 4, 14 and 16 feet. Bio-filter facility Asphalt parking lot and private drive Athletic fields Entrance drive Sidewalks 							
Building Construction	 Parking garage: Cast In Place Concrete Community Center: Cast In Place Concrete Gym: Heavy Timber 							
Maximum loads	Loading information is presented below based on our correspondence with VMDO: Garage Loading (assuming 2 levels) Column loading: 750 kips Wall loading: 18 kips/linear foot Community Center Building column loading: 350 kips Wall loading: 12 kips/linear foot Gym roof columns: 200 kips							
Maximum allowable movement	Recreation Center, Parking Garage and Retaining Walls Total: 1-inch Differential: ½ inch over 50 feet							
Grading	Unknown at this time							
Cut and fill slopes	Assumed to be no steeper than 3H:1V (Horizontal to Vertical).							

2.2 Site Description

ITEM	DESCRIPTION
Location	The project site is located at the southwest corner of North George Mason Drive and North Park Drive. The site is listed under the address 300 North Park Drive, Arlington, Virginia
Existing Conditions	The site is the location of an existing two-story recreation center, playground and parking lot.
Current ground cover	Predominantly grass with an asphalt parking lot.





ITEM	DESCRIPTION
Existing topography	Accurate current site topographic information was not provided. Based on Arlington County topographic maps, ground elevations range from about 260 feet mean sea level (MSL) in the center of the site to 230 feet MSL in the northwest of the site.

Should any of the above information or assumptions be inconsistent with the planned construction, please let us know so that we may make any necessary modifications to this report.

3.0 **SUBSURFACE CONDITIONS**

A discussion of the subsurface conditions encountered during our subsurface exploration is presented in the following sections.

3.1 Site Geology

A review of the local geologic information indicates that the site is geologically located in a formation of Miocene sand and gravel, constituting a thin outlier of the Coastal Plain in the easternmost Piedmont Physiographic Province. The Coastal Plain Province consists of a sequence of consolidated deposits of gravel, sand, silt, and clay that are underlain at greater depths by crystalline rock of the Piedmont origin. In this area, Coastal Plain deposits are less than 40 feet thick.

Terrace deposits of the Quaternary Age are typically found along the ridges and elevated portions of the coastal plains. These deposits consist primarily of fine to medium sand with various amounts of silt, clay and quartz gravel. Relatively thin clay seams can be found within the Quaternary deposits; however, these clay layers are generally discontinuous.

The Coastal Plain soil is underlain by soil of the Piedmont Physiographic Province. The Piedmont is a rolling upland surface underlain by complexly folded and faulted crystalline rocks. These metamorphic rocks date to the Cambrian period. The rock units are generally fine to coarse grained, lustrous, greenish-gray to gray, reddish-weathering, quartz-rich schist, and lesser mica schist, phyllite, and gneiss. Veins of quartz boulders should be anticipated in this geology.

The onsite soils, as mapped by USDA Web Soil Survey, are *Urbanland-Sassafras-Neabsco Complex*. *Urbanland* soils have been disturbed from their natural state. *Sassafras-Neabsco Complex* soil has marginal infiltration characteristics, depth to hard bedrock greater than 50 feet and fair foundation support due to poor bearing capacities.





3.2 Typical Subsurface Profile

3.2.1 Subsurface Conditions

Based on the results of the borings, subsurface conditions can be generalized as follows.

Description	Approximate Depth to Bottom of Stratum (feet)	Material Encountered	Consistency/Density
Existing Fill	6.0 feet	Fine-grained fill consisting of: • Sandy Lean Clay with Gravel (CL) • Sandy Silt with Gravel (ML) Coarse-grained fill consisting of: • Clayey Sand (SC) with various amounts of gravel • Silty Sand (SM) with various amounts of gravel	Soft to very stiff Loose to dense
Stratum I Coastal Deposits	8.5 to 23.5 feet	 Fine-grained soil consisting of: Sandy Silt (ML) with various amounts of gravel Lean Clay (CL) with various amounts of sand and gravel Coarse-grained soil consisting of: Silty Sand (SM) with various amounts of quartz fragments and gravel Clayey Sand with Gravel and quartz fragments (SC) 	 Medium stiff to hard Loose to very dense
Stratum II Residuum	23.5 to 40 feet	Fine-grained soil consisting of: Sandy Silt (ML) trace mica, with various amounts of gravel Silty Clay (CL/ML) Coarse-grained soil consisting of: Silty Sand with Gravel (SM)	Medium stiff to very hard Very dense
Stratum III Weathered Schist	Unknown, Stratum extents to Maximum Depth Explored	Highly Weathered to Partially Weathered Schist with quartz boulder veins	Very dense

Split spoon refusal, defined as 50 blows per zero inches of spoon penetration, was encountered at Borings 12 and 13 at depths ranging from 53 to 63.5 feet. Competent rock was not encountered.





Based on rock coring performed at Boring 13, split spoon refusal occurred on quartz boulders. Veins of quartz boulders should be anticipated in this geology.

Specific conditions encountered at each boring location are indicated on the individual boring logs. Stratification boundaries on the boring logs represent the approximate location of changes in soil types; in situ, the transition between materials may be gradual. Details for each of the borings can be found on the boring logs included in Appendix A of this report.

3.2.2 Groundwater

The open boreholes were observed while drilling and 24 hours after completion for the presence and level of groundwater. Water was encountered at Borings B-7, B-11 and B-13 through B-16 at depths ranging from 13.5 to 21 feet beneath the existing ground surface.

Fluctuations in ground or perched water levels should be expected with variations in factors such as precipitation, surface run-off, construction activity, etc. It should be noted that the stratigraphy inferred from the test boring logs is approximate. Soil strata and groundwater conditions between test borings may vary from conditions observed at each test boring location.

3.3 Analytical

As outlined in the Client's site development criteria and based on our experience, the following analytical laboratory testing was performed by Terracon and independent analytical laboratories.

Moisture content, soil plasticity, percent fines

The results of the laboratory testing are presented on the individual boring logs and in Appendix B. Soil samples will be stored for a period 6 months following completion of the final report.

3.4 Infiltration Test Results

A total of two infiltration test holes (INF-1A and INF-1B), were prepared by using an ATV mounted drill rig augering to a depth of 5 feet. Solid 4-inch diameter PVC pipes were then installed inside these offset test holes. The test holes were then presoaked with 24 inches of water for a period of 24 hours prior to performing the infiltration tests. The following day, after the 24-hour presoak period, water level measurements were performed in the exploratory test borings and the offset infiltration test holes.

A field infiltration rate between 0.52 and 8.0 inches per hour is required for infiltration to be considered feasible based on Appendix 8-A of the 2013 DEQ Infiltration Practices specification.





Table II: Summary of Infiltration Test Results by Terracon

Test Hole	Test Depth (ft.)	Test Date	Time	Hourly Water Drop (inch/hr)	In-Situ Infiltration Rate (Avg.) (inch/hr)	USDA Textural Classification	Design Infiltration Rate (inch/hr)
INF-1A	17.0	6/15/2017	8:50 9:50 10:50 11:50	4.0 2.25 1.0 2.0	2.31	Loamy Sand	1.15
INF-1 B	17.0	6/15/2017	8:55 10:00 10:50 11:50	1.0 2.0 1.0 1.0	1.0	Loamy Sand	0.50

Soil samples obtained from test boring locations were classified as Loamy Sand. The tests indicate that the subsurface conditions meet the requirements for infiltration testing based on Virginia DEQ Stormwater design specification No. 8 requirements. Based on our field investigation, infiltration is feasible.

Design of infiltration facilities must meet the following conditions set in the Virginia DEQ Stormwater design specification No. 8:

- The invert of the proposed infiltration system must be separated from both the SHWT (Seasonal High Water Table) and bedrock by at least 2 feet.
- Infiltration systems must be located at least 20 feet (horizontal distance) from the foundations of buildings regardless of whether there is a basement.
- No portion of the invert of infiltration systems can be placed in fill soils.
- Infiltration systems must not be on finished slopes greater than 15 percent (6.7H: 1V).
- Infiltration systems must not be sited at a location which could cause water-related problems or slope instability on downslope properties.
- Infiltration systems must be located a minimum of 100 feet (horizontal distance) from septic fields.





4.0 GEOTECHNICAL EVALUATION AND RECOMMENDATIONS

The recommendations contained in this report are based on the field exploration performed at the project site.

It is our opinion that the subject property is suitable for the proposed building additions and site improvements. The following is a presentation of our recommendations regarding subgrade preparation and earthwork operations, fill placement, building foundations, ground-supported slabs, utility installation, seismic site classification and other design and construction considerations.

The major geotechnical considerations for the development of the site are:

- 1. A Seasonal High Water Table (SHWT) that is above or near the lowest floor elevation of the planned parking garage.
- 2. The demolition of the existing community center structure.

4.1 Existing Fills

Existing fills were encountered at several of the borings performed within the planned building areas extending to depths up to 5 feet below existing grades. All existing fills within the building additions should be proof-rolled, undercut, and evaluated by the Geotechnical Engineer of Record in accordance with **Section 4.4.1** of this report.

4.2 Suitability of On-site Soils

The non-organic onsite soils encountered in the borings are suitable for re-use as structural fill. In general, material with liquid limit and plasticity index values greater than 40 and 14 including high plasticity clays (CH) or elastic silt (MH) are not suitable for use as structural fill.

Onsite soils may be wet or dry of the optimum moisture required for compaction; therefore, scarifying and drying by spreading and aerating prior to their reuse as compacted structural fill or backfill should be expected.

4.3 Excavation of On-Site Soils

In general, we anticipate that conventional earth-moving equipment will be suitable for the excavation of the onsite soils to achieve proposed grades for building foundations and utility inverts.





4.3.1 Dewatering measures during Construction

We anticipate groundwater may be encountered due to localized perched conditions at foundation elevations during general earthwork construction activities. Groundwater can be handled through temporary dewatering methods, i.e. sump pits and continuous pumping, if work is planned during the wet period of the year. The groundwater table should be maintained at least 2 feet below the bottom of foundation elevation.

4.3.2 Temporary excavations

Temporary excavations greater than 4 feet shall be properly shored or sloped away from the excavation with a minimum grade of 1.5H to 1.0V (horizontal to vertical). If sloping of utility trenches and pits are not desired, then trench boxes should be utilized. All excavations shall be performed in accordance with the OSHA and VOSHA regulations.

Temporary shoring for shallow excavations, such as timber shoring, trench boxes, braced thickened steel plates, and steel sheet piles can be used after they have been designed and approved by a Virginia Registered Professional Engineer. These systems should provide temporary earth retention for near-vertical side slopes, and should provide protection against potential bottom heave of excavations due to groundwater. We recommend using trench boxes or design a shoring plan where the proposed excavations will be performed for utility lines, structures or foundations and located adjacent to existing roadways, structures and existing utility lines. The Contractor should provide measures to protect existing roadway, structures and utilities where present. Temporary support of excavations should be designed by a Virginia Registered Professional Engineer. The temporary support of excavations designs and details should be submitted to the Geotechnical Engineer of Records for review.

Excavations for the proposed underground two-level parking garage will require a temporary or permanent sheeting and shoring system. If a free draining system consisting of soldier piles and wood-lagging is planned, the system should be braced externally using tiebacks. However, adjacent structures and utilities may prevent tiebacks from being used. This condition should be reviewed by the design engineer. Lengths, size and spacing of soldier piles may vary at these locations.

The soldier piles and lagging should be designed for an active lateral earth pressure of 45 psf for every foot of vertical cut. Spacing of the soldier beams and braces should be designed by a Virginia Registered Professional Engineer. However, we recommend that the maximum centerline-to-centerline spacing of the soldier piles not exceed 6 feet. In addition, wooden lagging should have a minimum thickness of 4 inches.

If tiebacks are used, the tieback anchors must be situated beyond a 45-degree slope from the base of the excavation. We recommend that tiebacks be installed at a maximum downward angle of 20 degrees from the horizontal. We also recommend that a performance test be performed on





10 percent of the tiebacks (randomly selected). The performance test evaluates the tieback load carrying capacity, deflections during loading, and movements with respect to time.

In areas where tiebacks are not feasible, an internal bracing system consisting of rakers would be required. Rakers should be braced against toe blocks or other reaction points that have been designed to carry the load. All excavations shall be performed in accordance with the OSHA regulations.

4.4 Earthwork

4.4.1 Proof-rolling

All areas delineated and surveyed in the field to receive structural fill shall be proof-rolled with a fully-loaded rubber-tired dump truck with a minimum axle weight of 10 tons in order to identify all soft or unstable areas to be undercut. The geotechnical engineer or his assigned representative shall decide on the depth of undercut in order to avoid the removal of suitable or otherwise firm soils.

4.4.2 Structural Fill Material

All structural fill material, whether on-site or imported from an off-site source, shall be tested for suitability and quality prior to its use as fill or backfill. We recommend that the material be tested to determine particle gradation, plasticity, and maximum dry density. The following standard tests should be performed to determine the above properties of all structural fill material:

Particle Size Analysis of Soils ASTM D422
Atterberg Limits ASTM D4318
Standard Proctor ASTM D698

Structural fill material should consist of quality, low plasticity, inorganic soil that classify as GW, GP, GM, GC, SW, SP, SC, or SM in accordance with ASTM D2487. Structural fill may consist of soils that classify as ML and CL provided that the material has a liquid limit and plasticity index less than or equal to 40 and 14, respectively; and a maximum of 70% passing a U.S. Standard No. 200 sieve. All fill material should be inorganic, free of ice, snow, construction debris, rock sizes greater than 4 inches, expansive and high plasticity clay, or other deleterious material.

4.4.3 Fill Placement and Testing

Fill material placed in *pavement and sidewalk areas* should be placed in no greater than 8-inch loose lifts and compacted to at least 95% of the maximum dry density as determined per VTM-1 method (ASTM D-698). However, the final foot of fill in pavement should be compacted to 100% of the maximum dry density of the same standard. The fill material should consist of a minimum dry density of 100 pounds per cubic feet (pcf). The moisture content of the fill being placed should be within 2 percentage points of the optimum moisture content of the material. The controlled fill should extend a minimum of 2 feet laterally outside the curb line plus 1 foot for every foot of fill above the subgrade.





Fill materials in *building areas* should be placed in no greater than 8-inch thick loose lifts and compacted to at least 95% of the maximum dry density as determined in accordance with the Standard Proctor (ASTM D-698). When hand-held tampers are used to compact the backfill materials, lift thickness shall be reduced to not more than 6 inches. The moisture content of the fill being placed should be within 2 percentage points of the optimum moisture content of the material.

To ensure proper compaction efforts, field density determinations should be performed in accordance with specifications set forth in ASTM D6938 (nuclear method) or D1556 (sand cone method). We recommend that density tests be performed on every lift of compacted structural fill placed in building areas. The frequency of compaction tests should be performed in accordance with the Schedule of Inspections outlined by the Geotechnical Engineer of Record for this project.

4.5 Site Utilities

All loose or organic materials encountered at the utility pipe subgrade should be removed. The pipe subgrade should be observed and probed for density under the supervision of a Virginia-registered professional engineer or an approved representative to evaluate the suitability of materials encountered. Any relatively isolated, thin, soft or yielding areas should be undercut or replaced with suitable compacted fill or pipe bedding material in accordance with the requirements stipulated in this report.

4.6 Foundation Support

The proposed building additions can be supported on conventional shallow foundations such as continuous wall or column spread footings bearing on natural low-plasticity soils or approved compacted structural fill based on the column loads of 350 to 750 kips and wall loads of 12 to 18 kips/ft.

Existing fill soils were encountered in the test borings performed in the building addition areas extending to depths up to 6 feet. We recommend that all existing fill soils should be assessed within the building foundations. The areas may be undercut and replaced or improved at the direction of the geotechnical engineer.

- Community Center: footings supported on properly-compacted structural fill or natural soils may be designed for an allowable soil bearing pressure of 4,000 psf with spread footings.
- Parking Garage: Footings supported on natural low-plasticity soils may be designed for an allowable soil bearing pressure of 5,000 psf with spread footings.





Footing lines to be located along a transition zone from natural soils to recently-placed fill shall be reinforced with two (2) #5 bars which extends at least 5 feet horizontally in each direction from the transition plane.

As a minimum, wall footings shall not be less than 18 inches in width and column footings shall not be less than 30 inches in size. Adequate frost cover protection for all exterior footings shall be provided at 24 inches below finished exterior grade along the footing lines. Interior footings, however, that are located within permanently heated areas may be located at nominal depth below the floor slab elevation.

The use of the above specified uniform allowable bearing capacity will minimize the total settlement to 1 inch or less with differential settlement of less than ½ inch or less in accordance with standard engineering practices.

If CH/MH type soils are encountered at or near footing subgrade levels during construction, the excavation shall be made to at least 4 feet below planned bottom of footing, or through the CH/MH materials if less than 4 feet below finished exterior grade. The excavation shall be backfilled with granular material such as VDOT-21A, and compacted to backfilled requirements mentioned in section 4.4.3.

All footings and slabs shall be inspected for quality of the subgrade material, concrete formwork and placement of reinforcing steel. The inspection shall be performed by a qualified soil inspector under the direction of a registered Virginia-geotechnical engineer. The inspection shall consist of probing or performing Dynamic Cone Penetrometer (DCP) tests. If visual inspection of the subgrade material and/or hand auger recovery material reveals the presence of high plasticity soils, we recommend that a sample of the subgrade soil to be tested to ensure compliance with **Section 4.4.2** of this report. Footing subgrades should be protected from precipitation, seepage, surface run-off and frost. We recommend that the footings be cast the same day of excavation.

If higher building and column loads are anticipated, we recommend ground improvement prior to at foundations.

4.7 Ground-supported Slabs

We expect that floor slabs will be constructed as ground-supported concrete slabs bearing on approved natural soil or properly compacted structural fill with a modular of subgrade reaction of 150 pounds per cubic inch (pci). If visual inspection of the subgrade material within the cut portion of the pads reveals the presence of clay (CH) and elastic silt (MH), we recommend that the subgrade be undercut to a minimum of two (2) feet or to the depth of a suitable soil layer, whichever comes first and replaced with of properly compacted structural fill.





The existing fill soils in the building areas, as discussed in **Section 4.5** of this report, should be proof-rolled, undercut, and replaced as necessary in accordance with **Section 4.4.2**.

If visual inspection of the subgrade material within the cut portion of the pads reveals the presence of clay (CH) or elastic silt (MH), we recommend that the subgrade be undercut to a minimum of two (2) feet or to the depth of a suitable soil layer, whichever comes first and replaced with properly compacted structural fill.

If the existing fill soils, as discussed in **Section 4.4.1** of this report, are located within the offset stakeout of the proposed house pads, then it shall be evaluated by the geotechnical engineer and removed in its entirety if determined to be unsuitable, and replaced with suitable structural fill material.

We recommend that all grade slabs be designed to be discontinuous at walls and pier footings. The slab should rest upon a minimum of 4 inches of free draining granular base. In areas of the floor slab where loads are in excess of 500 psf, we recommend the granular material beneath the floor be increased to a minimum thickness of 6 inches, and additional reinforcing steel be placed in the floor slab. A 6-mil polyethylene liner or similar vapor barrier should be provided between the underside of the slab and the granular base to limit moisture migration. In addition, we recommend that wire mesh or fiber mesh reinforcement be included in the slab design. This reinforcement will minimize the crack width of any shrinkage cracks that may develop near the surface of the floor slab.

4.8 Seismic Site Classification

The borings at the building addition areas were each extended to the planned boring termination depths varying from 10 to 70 feet below the existing site grades. The natural soils encountered had SPT N-values on the order of 6 bpf to greater than 50 bpf. Although N-values greater than 50 blows per 0 inches of split spoon penetration were encountered,

The International Building Code (IBC) 2012 requires site classification based on the upper 100 feet of a soil profile. Based on the average N-values of the natural soils, we recommend that the design for the building be based on a seismic site classification of Site Class C.

4.9 Foundation Walls, Backfill and Drainage

The proposed buildings may be constructed with below grade foundation walls. The Final Basement Floor Elevation (BFE) is planned at approximately El. 236 to 252 feet MSL as per the site plans provided by the client. We recommend that these walls be designed for an equivalent fluid pressure of 60 psf per foot of wall depth. The equivalent fluid pressure is recommended based on the assumption that the backfill material may consist of on-site or imported soils which





classify as SILT or Sandy SILT (ML). Soils having liquid limit and plasticity index greater than 40 and 15, respectively, shall not be used for backfill against the foundation walls. Backfill material shall not contain rock sizes greater than 4 inches in diameter. An example of a typical foundation drainage detail is included as Figure 2.

The lateral pressure recommended above assumes that adequate drainage behind the wall will be provided to prevent accumulation of free water. The recommendations do not include the effects of surcharge loading which shall be included in the wall design as additional lateral pressure acting uniformly against the wall.

Interior and exterior foundation drains are required around the perimeter of the structures. The exterior drain shall consist of a 4-inch perforated flexible tube embedded in 12 inches of VDOT #57 stone or washed bank run gravel. The stone shall be wrapped with filter fabric (such as Amoco 4545) to avoid clogging with fines. The interior drain shall consist of a 4-inch diameter perforated flexible tube embedded in a 12-inch layer of VDOT No. 57 stone wrapped with geotextile filter fabric. The interior drain shall be installed under the slab and shall tie into the exterior drain via weep holes through the footings. The weep holes, 1.5-inch diameter PVC pipes, shall be spaced at no more than 8 feet on center. An example of an appropriate foundation drain is included as Figure 10 located at the end of this report.

If possible, the invert of the interior drain shall be higher than the exterior drain to allow the flow of groundwater through the weep holes and safely discharge away from the structures. The outlet pipe from the exterior drain shall be tied to the storm sewer or discharge to a point of daylight or a sump pit as directed by the Civil Engineer. However, if daylighting of collected water to lower elevations is not feasible, the invert of the interior drain shall be lower than the exterior drain to allow the flow of groundwater through the weep holes to the sump. If elevator pits extend below the lowest floor slab, the elevator pit shall then be waterproofed and designed for full hydrostatic pressure.

Additionally, we recommend the installation of drainage board behind the foundation wall to minimize hydrostatic pressure. These drainage boards include Geotech drains, Enka Drains, Mira drains or equivalent. After installation, the walls may be backfilled with approved free draining material as specified earlier. If there are any "steps" within the building where there are grade changes, all below grade walls thus developed should have perimeter drain lines installed in the "uphill" side of the slab, which is then directed to flow by gravity into a suitable outlet.

Based on water levels observed within the borings, we anticipate that seasonal perched groundwater levels may rise to foundation elevations for the parking garage during the wet periods of the year, i.e. between November and May. Therefore, exterior foundation drain should consist of a 4-inch perforated flexible tube embedded in 12 inches of VDOT #57 stone or washed bank run gravel. The stone should be wrapped with filter fabric to avoid clogging with fines. Alternatively, a prefabricated drainage system such as a J-Drain may be installed per the manufacturers guidelines. If drainage by gravity is not feasible, the invert of the exterior drain shall be located above the invert of the interior drain and the interior drainpipe shall be extended to the sump pump. The outlet pipe from the exterior





drain or the sump pump shall discharge to a daylight point as directed by the Civil Engineer.

4.10 Retaining Wall Recommendations

The undated site plan provided to us for the preparation of this report indicates that there are four retaining walls planned. These walls are described below:

Retaining Wall Location	Maximum Retaining Wall Height (ft)
Ramp between Community Center and	14.0
Parking Garage	
Northwest of Community Center	16.0
North of Community Center	4.0

The retaining walls may be constructed as mechanically stabilized earth (MSE) walls, gravity walls or concrete cantilever walls. The following recommendations are provided to assist the project team during the planning and design phases of the retaining wall.

The structural design of retaining walls should be performed in accordance with generally accepted engineering procedures that include minimum factors of safety (FOS) against global stability (FOS:1.25), sliding (FOS:1.5), and overturning (FOS: 2.0).

We recommend that retaining wall footings be supported on approved natural soils or structural fill and the western retaining wall footings be designed for a maximum allowable soil bearing pressure of 4

,000 psf. All footings shall be inspected for quality of subgrade material. High plasticity soils, if encountered at footing subgrade, shall be undercut approximately 4 feet and replaced with properly compacted structural fill. Since the retaining walls are free to rotate, we recommend the following soil parameters be used for the wall design:

Strata - Soil	Bulk Unit	3		Coefficient of Earth Pressure				
Description	Weight (pcf)	Internal Friction	(psf)	Active (K _a)	Passive (K _p)	At Rest (K ₀)		
Backfill (SM)	125	30	0	.33	3.00	.50		

The recommendations are based on the assumption that the walls will be designed to use on-site or off-site borrow materials that classify as sandy SILT (ML) or Silty SAND (SM) having a liquid limit and plasticity index not to exceed 40 and 14, respectively. We recommend that all backfill material be placed in no greater than 8-inch loose lifts and compacted to at least 95% of the maximum dry density as determined in accordance with specifications set forth in ASTM D698 (Standard Proctor).





Retaining walls shall be permanently drained by the installation of a 2-foot thick layer of gravel behind the wall that ties into a 6-inch perforated PVC pipe at the bottom of the wall. Filter fabric shall be used behind the gravel layer to prevent clogging of the gravel with fines. Solid outlet pipes connected to the perforated pipe shall be extended to a safe daylight point away from the wall.

4.11 Pavement Subgrade Preparation

For the design and construction of exterior asphalt or concrete pavements (parking garage, ramps and sidewalks) we recommend that all procedures outlined in this report be followed through the establishment of subgrade elevations. The subgrade for paved areas shall consist of natural low plasticity natural soils or approved compacted structural fill.

If fine-grained soils having liquid limit and plasticity index values greater than 40 and 15, respectively, are encountered at proposed subgrade elevations, these materials shall be undercut to a minimum depth of 2 feet below pavement subgrade and replaced with properly compacted structural fill.

Prior to placement of subbase stone, the subgrade shall be proof-rolled with a loaded dump truck to detect any soft, yielding or high plasticity soils. Unstable areas shall be undercut and replaced with controlled-compacted fill. The fill shall be compacted per **Section 4.4.3**

As the engineering characteristics of the onsite soils vary throughout the site, CBR tests should be performed within the proposed pavement areas at the time of construction in order to permit proper pavement design. However, for preliminary design purposes, an average CBR value between 10 may be anticipated for subgrade soils consisting of on-site fine-grained soils. All pavement materials and construction methods shall comply with current VDOT specifications.

Subgrade soils placed in pavement areas shall be placed in no greater than 8-inch loose lifts, and compacted to at least 95% of the maximum dry density as determined per VTM-1 method. However, the final 2 foot of fill should be compacted to 100% of the maximum dry density as determined per VTM-1 method. The moisture content of the material being placed shall be within 2 percentage points of the optimum moisture content of the material.

Recommended Minimum flexible pavement sections							
Layer	Thickness (inches)						
Layei	Light Duty	Medium Duty					
Bituminous Surface Course	1- 1/2	1- 1/2					
Intermediate Course	-	1- 1/2					
Base Course	3	3					
VDOT-21A	6	8					





The pavement sections recommended are not designed for construction traffic. Damaged areas due to construction traffic should be repaired prior to placement of final asphalt surface course.

A rigid pavement section, consisting of Portland cement concrete, is recommended in areas of concentrated traffic loads, such as near the trash dumpster area, compactor pads, entrance/exit aprons and truck access roads. We recommend at least 6 inches of PCC be placed over minimum 6 inches of VDOT-21A aggregates. Welded wire fabric reinforcement should be installed within the pavement section. A modulus of subgrade reaction of 150 pci may be used for concrete pavement design.

4.12 Bio-Filter Facility

The site is planned for the installation of an underground bio-filter facility. Groundwater was not encountered in the vicinity of the bio-filter facility. Details of the facility were not available at the issuance of this report. During the installation of the facilities, perched groundwater may be encountered and should be allowed to drain prior to installation. However, after installation of the facilities, perched water infiltration into the drains is anticipated to be limited and have no significant impact on the proper functioning of the detention facilities.

One (1) soil profile boring was drilled to a depth of nineteen feet below ground inside the footprint of the proposed bio-filter facility. The proposed invert of the facility is 250.0 feet MSL. Groundwater was not encountered. Two (2) test pits were excavated within the footprint of the proposed bio-filter facility. The test pits were analyzed by a professional engineer certified in Soil Morphology by the Northern Virginia Soil and Water Conservation District. Indications of the seasonal high water table were not encountered within the excavated depth.

If unsuitable soils, such as high plasticity clay (CH) and elastic silt (MH) with Liquid Limit greater than 40 percent and Plasticity Index greater than 14 percent, are encountered beneath detention facility, they should be undercut and replaced with engineered fill in compliance with **Section 4.4.2.** These high plasticity soils shall not be used as subgrade support for the bio-filter facility. They are known to possess high shrink-swell potential and plastic behavior. Unsuitable soils are classified as soils consisting of organics, ice, snow, construction debris, rock sizes greater than 4 inches, expansive and highly plastic clay/silt, or any other deleterious material.

After stripping of topsoil and any soft surface soils, the subgrade soils encountered within the general vicinity of the SWM facility are considered to be generally suitable for use as fill. All soft, yielding subgrade soils shall be undercut to a bearing stratum approved by the geotechnical engineer or his assigned representative.





5.0 CLOSING REMARKS

5.1 Additional Services

We recommend that quality control testing and geotechnical engineering consulting services be provided during the construction phase of this project. These services shall include:

- Observe undercutting of unsuitable soils and inspect the subgrade for building foundation;
- Perform laboratory testing of material proposed for use as structural fill;
- Perform compaction testing during the placement of approved structural fill material;
- Verify soil bearing capacity and foundation inspections.

These inspections and field testing services shall be performed by a qualified soil and concrete inspector under the supervision of a Virginia-registered professional engineer. Terracon will be pleased to furnish these and other services during the design and construction phases of the project.

5.2 GENERAL COMMENTS

Terracon should be retained to provide observation and testing services during grading, excavation, foundation construction and other earth-related construction phases of the project.

The analysis and recommendations presented in this report are based upon the data obtained from the borings performed at the indicated locations and from other information discussed in this report. This report does not reflect variations that may occur across the site, or due to the modifying effects of weather. The nature and extent of such variations may not become evident until during or after construction. If variations appear, we should be immediately notified so that further evaluation and supplemental recommendations can be provided.

The scope of services for this project does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions.

Please be advised that although the soil borings and were logged by experienced engineers, it is sometimes difficult to record changes in subsoil stratigraphy within narrow limits; therefore, some deviation in the materials reported on the field logs and the materials encountered at the site should be anticipated. Any change in soil type observed during construction, or change in proposed location






of the structures or grades should be provided to us so that we may have the opportunity to amend the content of this report, if necessary. Any conclusions or recommendations based on data contained in this report that are made by others are the responsibility of others.

This report has been prepared for the exclusive use of our client for specific application to the project discussed and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, either express or implied, are intended or made. Site safety, excavation support, and dewatering requirements are the responsibility of others. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless Terracon reviews the changes and either verifies or modifies the conclusions of this report in writing.



APPENDIX A FIELD EXPLORATION

ckingham Arlingt Height U-S RES ARLINGTON HAL Adlington TOPOGRAPHIC MAP IMAGE COURTESY OF THE U.S. GEOLOGICAL SURVEY QUADRANGLES INCLUDE: FALLS CHURCH, VA (1/1/1994), WASHINGTON WEST, DC (1/1/1983), ANNANDALE, VA (1/1/1994) and ALEXANDRIA, VA (1/1/1994). Project Manager: Project No. SITE LOCATION Exhibit EW175052 Scale: 1"=2,000 Drawn by: WK Lubber Run Recreation Center A-1 File Name: EW175052.a1 Checked by: Bowman Consulting Group 300 North Park Drive, Arlington, VA 21505 Greenoak Way DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION Dulles, VA 20166-9225 Approved by: PURPOSES 6/23/2017







Field Exploration Description

The boring locations were located by measuring from existing site features and obtaining latitude / longitude with a hand-held GPS unit. Geographic coordinates were converted to Virginia State Plane Northing / Easting coordinates using computer software. Ground surface elevations were estimated using topographic site drawings provided by Bowman Consulting. The locations of the borings and elevations should be considered accurate only to the degree implied by the means and methods used to define them.

The borings were drilled with 4-1/4 inch hollow stem augers or mud rotary methods using a 2-15/16 inch tri-cone bit utilizing a CME 550 drill rig mounted on a track carrier equipped with an automatic hammer. Samples of the soil encountered in the borings were obtained using the split barrel sampling procedures. The samples were tagged for identification, sealed to reduce moisture loss, and taken to the laboratory for further examination, testing, and classification. Following the completion of drilling, the boring was backfilled with soil cuttings.

A CME automatic SPT hammer was used to advance the split-barrel sampler in the boring performed on this site. A greater efficiency is typically achieved with the automatic hammer compared to the conventional safety hammer operated with a cathead and rope. Published correlations between the SPT values and soil properties are based on the lower efficiency cathead and rope method. This higher efficiency affects the standard penetration resistance blow count (N) value by increasing the penetration per hammer blow over what would be obtained using the cathead and rope method. The effect of the automatic hammer's efficiency has been considered in the interpretation and analysis of the subsurface information for this report.

Field logs of the borings were prepared by Terracon's representative. The logs included visual classifications of the materials encountered as well as interpretation of the subsurface conditions between samples. The boring logs included with this report represent the engineer's interpretation of the field logs and include modifications based on laboratory evaluation of the samples. The boring logs are presented in Appendix A. General notes to log terms and symbols are presented in Exhibit C.

Rock Coring

Split spoon refusal was encountered at borings B-12 and B-13. Samples of quartz boulders and highly weathered rock were obtained using a NQ sized core barrel with a diamond cutting bit. The core sample recovered with the core barrel is approximately 1.9 inches in diameter. The distance cored was 10 feet.



	BORING	LOG NO. B-	1				F	Page 1 of	1
PF	ROJECT: Lubber Run Recreation Center	CLIENT: Bowr	nan (Cons	ulti Bo	ng It Place S	uite 300		
SI	TE: 300 North Park Drive Arlington, Virginia								
GRAPHIC LOG		Surface Elev: 246 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI	
	DEPTH 0.2 \(\tag{TOPSOIL} (2") \) FILL - SANDY SILT WITH GRAVEL, brown, soft, moist.	ELEVATION (Ft.)	_		X	4-2-2 N=4			
2	2.5 FILL - SILTY SAND WITH GRAVEL, light brown, dense, moist	243.5+/-	_						
3DT 6/24/	FILL - SILIT SAND WITH GRAVEL, light blown, dense, moisi	•	_		Д	15-16-21 N=37			_
ATATEMPLATE. C	5.0 SANDY LEAN CLAY (CL), reddish brown, medium stiff, moist.	241+/-	5 — –		X	8-4-5 N=9			
RACON_D/	8.5	237.5+/-	_						
GPJ TER	SILTY SAND (SM), greyish brown, loose to dense, moist.		- 10-		X	6-4-5 N=9			
NO WELL EW175052 LUBBER RUN RECREA,GPJ TERRACON_DATATEMPLATE,GDT 6/24/17			_						
175052 LUBBE			- 15-		X	8-10-12 N=22			
LOG-NO WELL EW			- -						
GEO SMART LOG-			20-		X	15-20-22 N=42	!		
			_						
RIGINAL	23.6	222.5+/-	_			F0/4"			
O FROM O	Boring Terminated at 23.6 Feet				١	50/1" N=50+	_		
PARATE	Stratification lines are approximate. In-situ, the transition may be gradual.		Ham	ımer Ty	/pe: /	Automatic			
HS Aban	See Appendix B for procedures and add	description of laboratory	Notes	S :					
16 LOG 18	WATER LEVEL OBSERVATIONS		Boring	Starte	d: 6/1	2/2017	Boring Com	pleted: 6/12/20	017
IS BORIN		Facon Greenoak Way	Drill Ri	g: CME	E 550	/AT V	Driller: Reco	on Drilling	
王 1288 組		ulles, VA	Project	t No.: E	W17	5052	Exhibit: A	\-4-1	



		BORING L	OG NO	. B-	2				F	Page 1 of 1
PR	OJECT: Lubber Run Recreation Center	,	CLIENT:	Bowr 14020	nan (Cons	ulti Bo	ng It Place Si	uite 300	
SIT	E: 300 North Park Drive Arlington, Virginia									
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.873525° Longitude: -77.114222° DEPTH	Approximate Sur	rface Elev: 248 (ELEVATIO		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	0.1.\TOPSOIL (1") FILL - SILTY SAND WITH GRAVEL, reddish moist.	brown, medium den		248+//	_	-	X	6-8-10 N=18		
					- -	-	X	15-10-14 N=24		
	POORLY GRADED SAND WITH SILT AND Go brown, dense, moist.	RAVEL (SP-SM), red	ddish	243+/-	5 — -		X	8-15-17 N=32	5	NP
	8.5 SANDY SILT (ML), greyish brown, very stiff, n	noist.		239.5+/-	- -			8-8-9		
					10-			N=17		
	13.5 SILTY SAND (SM), greyish brown, dense, mo 15.0	ist.		234.5+/-	_		X	8-12-14 N=26		
Advand HSA	Boring Terminated at 15 Feet				15					
	Stratification lines are approximate. In-situ, the transition ma	y be gradual.			Ham	mer Ty	pe: A	Automatic		<u> </u>
Advan HSA Aband Bac	coment Method: conment Method: cfilled with Auger Cuttings	See Exhibit A-3 for desc procedures. See Appendix B for des procedures and addition See Appendix C for exp abbreviations.	cription of labora nal data (if any).	-	Notes	s:				
	WATER LEVEL OBSERVATIONS Groundwater not encountered		900	n	<u> </u>	Started			Boring Com	pleted: 6/15/2017
	Cave-in after 24 hours.	21505 Gre	enoak Way es, VA			ig: CME			Driller: Reco	on Drilling A-4-2



L	В	ORING L	OG NO	. В-	3				F	Page 1 of 1
PR	OJECT: Lubber Run Recreation Center		CLIENT:	Bown 14020	nan () Thu	ons nder	ultii Bo	ng It Place Sı	uite 300	
SIT	TE: 300 North Park Drive Arlington, Virginia									
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.8733554° Longitude: -77.113915° DEPTH	Approximate Sur			DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	0.2_\tag{TOPSOIL (2")} FILL - SANDY SILT, reddish brown, medium si	tiff, moist.	<u>ELEVATIO</u>	N (Ft.) 251+/			X	3-3-2 N=5		
	3.8 POORLY GRADED SAND WITH GRAVEL (SP).	brown medium d	ense to	247+/-	_		X	9-13-11 N=24		
	dense, moist.	, 5.5,			5 -			15-16-14 N=30	3	
	8.5 POORLY GRADED GRAVEL (GP), brown, dens	se, moist.	2	242.5+/-	_ _ _			17-20-14		
					10-			N=34		
	13.5 SANDY SILT (ML), yellowish brown, dense, mo	ist.	2	237.5+/-	- - 15-	\ /	X	8-16-18 N=34		
	Boring Terminated at 15 Feet									
	Stratification lines are approximate. In-situ, the transition may	be gradual.			Ham	mer Ty	pe: A	utomatic	\ 	· · · · · · · · · · · · · · · · · · ·
Advan HS/ Aband Bad	p S S P P S P P P P P P P P P P P P P P	iee Exhibit A-3 for descrocedures. iee Appendix B for descrocedures and additioniee Appendix C for expibbreviations.	cription of labora nal data (if any).	-	Notes	S :				
	WATER LEVEL OBSERVATIONS Groundwater not encountered	76	255		Boring	Started	: 6/15	5/2017	Boring Com	pleted: 6/15/2017
Advand HS/	Cave-in after 24 hours.	21505 Gre	enoak Way			g: CME			Driller: Reco	on Drilling A-4-3



	ROJECT: Lubber Run Recreation Center	CLIENT: Bow	man	Cons	sulti	ing		
SIT	TE: 300 North Park Drive Arlington, Virginia	1402	20 I NU	ınde	r Bo	olt Place S	uite 300	
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.873258° Longitude: -77.115367° DEPTH	Approximate Surface Elev: 248 (Ft.) +/- ELEVATION (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI
	0.2-∖TOPSOIL (2") SANDY SILT WITH GRAVEL, reddish brown, med		-		X	4-4-5 N=9		
			-		X	10-14-13 N=27	3	
	5.0 SANDY LEAN CLAY, reddish brown, hard, moist.	243+/	5-		X	10-15-22 N=37	2	
	8.5 SANDY SILT (ML), trace mica, reddish brown, vel	239.5+/ry stiff, moist.	- -			12-13-15	5	
	10.0 Boring Terminated at 10 Feet	238+/	10-		M	N=28	<u> </u>	
	Stratification lines are approximate. In-situ, the transition may be	gradual.	Har	nmer T	ype:	Automatic		
HS/ and	ncement Method: See proc See proc donment Method: See	gradual. Exhibit A-3 for description of field redures. Appendix B for description of laboratory redures and additional data (if any). Appendix C for explanation of symbols and reviations.	Note		ууре:	Automatic		
HSA and	ncement Method: See proc See proc donment Method: See	Exhibit A-3 for description of field sedures. Appendix B for description of laboratory sedures and additional data (if any). Appendix C for explanation of symbols and reviations.	Note	es:			Parine Co.	plated 0/43/20
HSA and	ncement Method: See proc See proc donment Method: ckfilled with Auger Cuttings	Exhibit A-3 for description of field sedures. Appendix B for description of laboratory sedures and additional data (if any). Appendix C for explanation of symbols and	Note d Boring	es:	d: 6/1	3/2017	Boring Com Driller: Reco	pleted: 6/13/20



[]		BORING LO	OG NO. B-	5				F	Page 1 of 2
PR	OJECT: Lubber Run Recreation Center	r	CLIENT: Bowr 14020	nan (Cons	ulti	ng		
SIT	E: 300 North Park Drive Arlington, Virginia		14020	v inu	nuel	DO	n Fiace S	uite 300	
90	LOCATION See Exhibit A-2				EL NS	PE	<u> </u>	(%	ATTERBERG LIMITS
GRAPHIC LOG	Latitude: 38.873319° Longitude: -77.114943°	Approximate Sur	face Elev: 253 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	LL-PL-PI
	DEPTH 0.1_\TOPSOIL (2")	-41ff	ELEVATION (Ft.)		- 0	Š,	2-3-3		
	FILL - SANDY LEAN CLAY, brown, medium	Stiff, Moist.		_		\triangle	N=6		
· · · · · · · · · · · · · · · · · · ·	2.5 SILTY SAND, reddish brown, dense to very d	lense, moist.	250.5+/-	_		\bigvee	5-6-25		
				_		\triangle	N=31		
Altıvır Latı	With quartz fragments below 5.0 feet.			5 -		X	15-17-22 N=39		
				-					
STO CLOS				- 10-		\times	50/5" N=50+		
SON MECHANICAL CONTROLL OF THE CONTROL OF THE				-					
				_	28	X	18-6-7 N=13		
NO WELL EWIT 3002 LOBBER NON NECKEA, OF 3 TENANCON_DATABLEMIT LATE; OUT 0/24/11				15 - - -	102000				
				-			6-7-14 N=21		
				20-			N-21		
	23.5		229.5+/-	_					
	HIGHLY WEATHERED TO PARTIALLY WEA brown, very dense, moist.	THERED SCHIST, gr		_		\times	50/5" N=50+		
} × ×	Stratification lines are approximate. In-situ, the transition ma	ay be gradual.		25 Ham	mer Ty	ype: A	Automatic		
Advand HS/	cement Method:	See Exhibit A-3 for desc procedures. See Appendix B for desc procedures and addition	cription of laboratory	Notes	S :				
Aband Bac	onment Method: xfilled with Auger Cuttings	See Appendix C for expl abbreviations.							
	WATER LEVEL OBSERVATIONS Groundwater not encountered	Terr	əcon	Boring					pleted: 6/14/2017
	Cave-in after 24 hours.	21505 Gree Dulle	enoak Way	Drill Ri				Driller: Reco	on Drilling



	E	BORING L	OG NO. B-	5				ſ	Page 2 of 2
PR	OJECT: Lubber Run Recreation Center		CLIENT: Bowr 14020	man C	Cons nder	ulti Bo	ng It Place S	uite 300	
SIT	E: 300 North Park Drive Arlington, Virginia								
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.873319° Longitude: -77.114943°	Approximate Sur	face Elev: 253 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	HIGHLY WEATHERED TO PARTIALLY WEAT brown, very dense, moist. (continued)	T HERED SCHIST , gr	ELEVATION (Ft.) reyish			0,			
				30-			50/2" N=50+		
$\stackrel{\checkmark}{\times}$	33.6 Boring Terminated at 33.6 Feet		219.5+/-	_			50/1" N=50+		
	Stratification lines are approximate. In-situ, the transition may	y be gradual.		Ham	mer Ty	pe: A	Automatic		
HSA		See Exhibit A-3 for desc procedures. See Appendix B for desc procedures and addition	cription of laboratory al data (if any).	Notes	3 :				
	kfilled with Auger Cuttings	See Appendix C for explabbreviations.	anauon oi symbois and						
	WATER LEVEL OBSERVATIONS Groundwater not encountered	Terra	əcon	Boring Drill Ri				Boring Com Driller: Reco	pleted: 6/14/201
129	Cave-in after 24 hours.	21505 Gre Dulle	enoak Way	Project					A-4-5



		В	ORING LO	OG NO. B-	6					Page 1 of 1	1
Ī	PR	OJECT: Lubber Run Recreation Center		CLIENT: Bowr 14020	nan C	Cons	ulti	ng			
ŀ	SIT	E: 300 North Park Drive		14020	Jinu	naei	ВС	oit Place 5	uite 300		
ļ		Arlington, Virginia								ATTERBERG	
	CL06	LOCATION See Exhibit A-2			(Ft.)	WATER LEVEL OBSERVATIONS	TYPE	EST	#H (%)	LIMITS	
	GRAPHIC LOG	Latitude: 38.873664° Longitude: -77.11453°			DEPTH (Ft.)	TERL	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	LL-PL-PI	
	GR	DEPTH	Approximate Surf	face Elev: 252 (Ft.) +/- ELEVATION (Ft.)	□	WA	SAN	ᇤᄯ	8		
		0.2_\TOPSOIL (2") CLAYEY SAND (SC), brown, medium dense, m	noist.	\^252+ <i>b</i>	_		X	5-6-6 N=12			
				242.5.4	_		$\overline{}$				
24/17		SILTY SAND (SM), light brown, dense to very c	lense, moist.	249.5+/-	_		\forall	14-28-14			
3DT 6/					_		\triangle	N=42			
LATE.0					5 —		$\overline{}$	45.00.00			
4TEMP					_		X	15-22-26 N=48			
N_DAT					_	1888A					
RACOI					_						
N TER					-		XI	27-33-25 N=58			
REA.GF					10-						
N REC											
ER RU											
GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17	Ш	SANDY SILT (ML), greyish brown, very stiff, me	oist.	238.5+/-	_		\forall	4-6-11			
W17505	Ш				15-		\triangle	N=17			
ELL EV	Ш				_						
M ON-	Ш				_						
ST LOG	Ш				_						
S SMAF	Ш	20.0		232+/-	_		XI	4-14-17 N=31	20	50-33-17	
	1111	Boring Terminated at 20 Feet		20217-	20-						
EPOR											
INAL R											
M ORIG											
D FRO											
THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.		Stratification lines are approximate. In-situ, the transition may	be gradual.		Ham	mer Ty	/pe: /	Automatic	l	1	•
IF SEP	Advan HSA		See Exhibit A-3 for desc rocedures.	ription of field	Notes	3:					
VALID	_,	S	Gee Appendix B for descrocedures and addition	cription of laboratory al data (if any).							
S NOT		onment Method:		anation of symbols and							
3 106 1		WATER LEVEL OBSERVATIONS			Boring	Starte	d: 6/1	5/2017	Boring Com	npleted: 6/15/20	017
SORING		Groundwater not encountered	llerra	econ	Drill Ri				Driller: Rec		J 1 1
THISE		Cave-in after 24 hours.	21505 Gree Dulles		Project				Exhibit:	A-4-6	



	BORING	LOG NO. B-	7				F	Page 1 of 1
PR	OJECT: Lubber Run Recreation Center	CLIENT: Bow 1402	man (0 Thu	Cons Inde	ulti Bo	ing olt Place S	uite 300	
SIT	TE: 300 North Park Drive Arlington, Virginia							
GRAPHIC LOG	1	e Surface Elev: 254 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI
	DEPTH 0.2_\TOPSOIL (2") FILL - SILTY SAND WITH GRAVEL, brown, medium dense, r	ELEVATION (Ft.) 254+/ noist.	-		X	5-5-6 N=11		
	2.5 SILTY SAND (SM), trace clay, reddish brown, loose to very de	251.5+/- ense, moist.	_	_	X	5-5-5 N=10		
			5-	- ,	X	6-10-14 N=24		
			- 10-		X	15-23-32 N=55	2	
			_ _ _			23-37-6		
	15.0 Boring Terminated at 15 Feet	239+/-	15-		Δ	N=43		
	Stratification lines are approximate. In-situ, the transition may be gradual.		Han	nmer Ty	/pe:	Automatic		
HSA Aband	See Appendix B for procedures and add	description of field description of laboratory ditional data (if any). explanation of symbols and	Note	s:				
∇	WATER LEVEL OBSERVATIONS While drilling		Boring	Starte	d: 6/1	15/2017	Boring Com	pleted: 6/15/2017
	21505	Facon Greenoak Way		ig: CME			Driller: Reco	
	Cave-in after 24 hours.	Dulles, VA	Projec	t No.: E	W17	75052	Exhibit: A	\-4-7



		OKING L	OG NO. B-					F	Page 1 of 1
	OJECT: Lubber Run Recreation Center		CLIENT: Bowr 14020	nan () Thu	Cons nder	ultii Bo	ng It Place S	uite 300	
SIT	E: 300 North Park Drive Arlington, Virginia								
GRAPH	LOCATION See Exhibit A-2 Latitude: 38.873138° Longitude: -77.115392° DEPTH	Approximate Sur	face Elev: 251 (Ft.) +/- ELEVATION (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	7.3_TOPSOIL (3") FILL - SANDY SILT, reddish brown, medium st	iff, moist.	250.5±/>	_		X	3-3-3 N=6		
	2.5 SILTY SAND (SM), with quartz fragments, greyi moist.	sh white, very den	248.5+/- se,	-		X	17-35-35 N=70		
				5 -		X	30-32-25 N=57		
				10-		X	27-27-15 N=42		
000000				- -					
000	No quartz fragments at 13.5 feet.		236+/-	- 15-		X	5-6-7 N=13		
	Boring Terminated at 15 Feet								
	Stratification lines are approximate. In-situ, the transition may be	pe gradual.		Ham	ı l ımer Ty	rpe: A	Automatic		1
HSA bando	proment Method:	ee Exhibit A-3 for descrete. ee Appendix B for descrete and addition ee Appendix C for exploreviations.	cription of laboratory	Notes	s:				
	WATER LEVEL OBSERVATIONS	7.		Boring	Started	N 6/11	3/2017	Boring Com	pleted: 6/13/201
	Groundwater not encountered	llerra	econ	<u> </u>	g: CME			Driller: Reco	-
33 2	Cave-in after 24 hours.	21505 Gree Dulle	enoak Way		t No.: E				A-4-8



		BORING L	OG NO.	B-9				ı	Page 1 of 2
	OJECT: Lubber Run Recreation Cente	r	CLIENT: B	owma 4020 7	an Co Thun	nsul der B	ting olt Place S		_
SIT	E: 300 North Park Drive Arlington, Virginia								
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.873115° Longitude: -77.114954°	Approximate Sur	face Elev: 260 (Ft.	´	DEPTH (Ft.)	OBSERVATIONS SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	DEPTH 0.2_\TOPSOIL (2") FILL - CLAYEY SAND, trace mica, brown, lo	ose, moist.	ELEVATION ((Ft.) (60+//		X	4-4-5 N=9		
	2.5		257	7.5+/-	_				
	<u>CLAYEY SAND (SC)</u> , with quartz fragments, dense to dense, moist.	reddish brown, medi				X	4-6-6 N=12		
					5 —	X	6-7-8 N=15		
	8.5 SILTY SAND (SM), with quartz fragments, lig	ht hrown dense to v		1.5+/-					
	dense, moist.	in biowii, ucibe lu V	Ci y		10-	X	22-27-25 N=52	5	
					 8				
				1	15— — —	X	17-18-14 N=32	1	
	SANDY SILT (ML), trace mica, brown, hard, i	moist.	241	1.5+/-	20-	X	10-20-22 N=42	2	
					-				
	25.0		23	35+/-	25 -	X	15-20-24 N=44	ı	
	Stratification lines are approximate. In-situ, the transition ma	ay be gradual.				er Type:	Automatic		
HSA Aband	cement Method: conment Method: filled with Auger Cuttings	See Exhibit A-3 for deso procedures. See Appendix B for des procedures and addition See Appendix C for exp abbreviations.	cription of laborator nal data (if any).	ry	Notes:				
) Bac	WATER LEVEL OBSERVATIONS						· · · · · · · · · · · · · · · · · · ·	n	
	Groundwater not encountered	llerra	əcor	7		cME-55	/13/2017 50/ ATV	Boring Com Driller: Rec	pleted: 6/13/2017 on Drilling
1888	Cave-in after 24 hours.		enoak Way es, VA	P	roject N	lo.: EW1	75052	Exhibit: /	\-4-9



ľ	BORING	G LOG NO. B-1	1				F	Page 1 of 2	2
PR	OJECT: Lubber Run Recreation Center	CLIENT: Bowr	man C	ons	ultir	ng It Place Si		_	
SI	TE: 300 North Park Drive Arlington, Virginia	14020	J I Mui	nuer	DO	IL PIACE SI	uite 300		
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.873268° Longitude: -77.114263° Approxi	mate Surface Elev: 256 (Ft.) +/- ELEVATION (Ft.)	DEРТН (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI	
	0.2_\TOPSOIL (2") FILL - SANDY SILT, reddish brown, stiff, moist.	^256+l/	-		X	4-5-6 N=11			
	2.5 FILL - CLAYEY SAND, reddish brown, medium dense, mo	253.5+/- pist.	-			12-9-13 N=22			
	5.0 CLAYEY SAND (SC), brown, dense, moist.	251+/-	5 — –	S	X	13-20-29 N=49			
GEO SWAM LOGINO WELL EWITHOUS LOBBER NON NECKENGRY TENNON_ON_ON THEIR ENTERNITY OF THE COLD OF SHIP			10-	S		40-42-37 N=79			
S S S S S S S S S S S S S S S S S S S			- - -						
EWIT 3002 FORD	13.5 SILTY SAND (SM), greyish brown, medium dense to dense	242.5+/- e, moist.	_ 15—		X	5-5-7 N=12			
LCG-INO WELL			-	New A					
			20-	2	X	7-11-13 N=24			
AGIINAL NELON			-						
			_ 25 _		\bigvee	12-18-17 N=35			
	Stratification lines are approximate. In-situ, the transition may be gradual.		Hami	mer Ty	pe: A	utomatic	<u> </u>	<u>. </u>	
Abano	procedures. See Appendix I procedures and	for description of field For description of laboratory additional data (if any). C for explanation of symbols and	Notes	:: ::					
	WATER LEVEL OBSERVATIONS		<u> </u>	01 .		100.47	.		
Z Z	After 24 hours	rracon	Boring					pleted: 6/15/20	17
	Cave-in after 24 hours.	505 Greenoak Way Dulles, VA	Drill Ric				Driller: Reco		



		ORING LC	OG NO. B-1	11				1	Page 2 of	2
PRO	JECT: Lubber Run Recreation Center		CLIENT: Bown	nan C	Cons	ulti	ng olt Place S			
SITE	300 North Park Drive Arlington, Virginia		14020) inu	naer	ВС	oit Place S	uite 300		
GRAPHICLC	OCATION See Exhibit A-2 atitude: 38.873268° Longitude: -77.114263°	Approximate Sur	face Elev: 256 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS	
	3.5 HIGHLY WEATHERED SCHIST, greyish brown Boring Terminated at 34.4 Feet		222.5+/-	30-			18-26-21 N=47 22-50/5" N=50+			
Advance HSA Abandon	ment Method:	y be gradual. See Exhibit A-3 for desc procedures. See Appendix B for desc procedures and addition See Appendix C for expl abbreviations.	cription of laboratory all data (if any).	Ham Notes		/pe: /	Automatic			
	After 24 hours Cave-in after 24 hours.	21505 Gree		Boring Drill Ri		550	/AT V	Boring Com Driller: Rec Exhibit: A)17

PROJEC [*]	T: Lubber Run Recreation Ce	BORING LO	CLIENT: Bow	man (Cons	ulti	ng		Page 1 of
			1402	0 Thu	ındei	r Bo	It Place S	uite 300	1
SITE:	300 North Park Drive Arlington, Virginia								
g LOCAT	ION See Exhibit A-2			÷	ŒL ONS	'nΕ	L.	(%	ATTERBERG LIMITS
GRAPH	38.873189° Longitude: -77.114739°	Approximate Sui	rface Elev: 260 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	LL-PL-PI
DEPTH 0.1.\TC	PSOIL (1")		ELEVATION (Ft.) /\260+//				8-8-6		
FIL me	L - CLAYEY SAND WITH ASPHALT And the dium dense, moist.	AND GRAVEL, reddish b	rown,	_	_	\bigwedge	N=14		
X				_		\bigvee	14-10-11		
3.5 LE	AN CLAY WITH SAND (CL), reddish b	prown, dense, moist.	256.5+/-	_		Д	N=21		
5.0			255+/-	5 -					
	AYEY SAND WITH QUARTZ FRAGME edium dense to loose, moist.	<u>ENTS (SC)</u> , reddish brow	n,	_	-	X	8-10-9 N=19		
				_					
30				_	_	X	5-4-2 N=6		
				10-		$\overline{}$			
%				_					
30				-					
13.5			246.5+/-	_					
bro	OORLY GRADED SAND WITH QAURT own, medium dense, moist.	<u>Z FRAMGMENTS (SP)</u> , II	gnt	_		X	30-32-40 N=72		
00				15–					
				_					
0 (_					
18.5	NDV OUT (MI)	ere	241.5+/-	_					
<u>5A</u>	NDY SILT (ML), trace mica, light brow	/n, stiff, moist.		_		X	4-8-6 N=14		
Ш				20-					
				_					
				_	1				
23.5	CUI V WEATHERED TO DARTIALLY	MEATHERED COURT	236.5+/-	-					
qu	GHLY WEATHERED TO PARTIALLY N artz boulders, greyish brown, very der	nse, moist.	nu i	_	1	X	17-30-50/5	5"	
X Stratific	cation lines are approximate. In-situ, the transiti	on may be gradual		25-	nmer T	vne. /	Automatic		
				. iaii		,pc. /			
dvancement M HSA	lethod:	See Exhibit A-3 for desc procedures. See Appendix B for des procedures and addition	cription of laboratory nal data (if any).	Note	s:				
	h Auger Cuttings	See Appendix C for exp abbreviations.	lanation of symbols and						
	TER LEVEL OBSERVATIONS dwater not encountered	75-6-	3605	Boring	Starte	d: 6/1:	2/2017	Boring Com	pleted: 6/12/2
			acon	Drill R	ig: CMI	E 550/	/AT V	Driller: Rec	on Drilling
Cave-ir	n after 24 hours.		enoak Way es, VA	Projec	t No.: E	<u>W</u> 17	5052	Exhibit: A	A-4-11



BORING LOG NO. B-12 Page 2 of 3 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE **GRAPHIC LOG** WATER CONTENT (%) FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.873189° Longitude: -77.114739° LL-PL-PI Approximate Surface Elev: 260 (Ft.) +/-**ELEVATION (Ft.)** DEPTH HIGHLY WEATHERED TO PARTIALLY WEATHERED SCHIST, with quartz boulders, greyish brown, very dense, moist. (continued) 39-50/5" N=50+ 30-50/4" N=50+ 35-40-50/2" N=50+ 40 50/1" N=50+ 45 50/1" N=50+ 50-Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/12/2017 Boring Completed: 6/12/2017 Groundwater not encountered Drill Rig: CME 550/AT V Driller: Recon Drilling 21505 Greenoak Way Cave-in after 24 hours Dulles, VA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17

Project No.: EW175052 Exhibit: A-4-11



BORING LOG NO. B-12 Page 3 of 3 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE **GRAPHIC LOG** WATER CONTENT (%) FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.873189° Longitude: -77.114739° LL-PL-PI Approximate Surface Elev: 260 (Ft.) +/-**ELEVATION (Ft.)** DEPTH HIGHLY WEATHERED TO PARTIALLY WEATHERED SCHIST, with quartz boulders, greyish brown, very dense, moist. (continued) GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17 207+/-50/0" Spoon refusal on quartz boulders at 53 Feet N=50+ Hammer Type: Automatic Stratification lines are approximate. In-situ, the transition may be gradual. Advancement Method: Notes: See Exhibit A-3 for description of field See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/12/2017 Boring Completed: 6/12/2017 Groundwater not encountered Drill Rig: CME 550/AT V Driller: Recon Drilling 21505 Greenoak Way Project No.: EW175052 Exhibit: A-4-11 Cave-in after 24 hours Dulles, VA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

		BORING LC	JG NO. B-1	3				F	Page 1 of	4
PROJEC	CT: Lubber Run Recreation Center	r	CLIENT: Bowr 14020	man C 0 Thur	ons nder	ultir Bol	ng It Place S	uite 300		
SITE:	300 North Park Drive Arlington, Virginia									
2	TION See Exhibit A-2 e: 38.873156° Longitude: -77.114126°	Approximate Sur	face Elev: 258 (Ft.) +/- ELEVATION (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI	-
0.4 A 0.5 \G	SPHALT (5") RAVEL (1") ILL - SANDY LEAN CLAY, brown, medium	stiff, moist.	257.5+/- 267.5+//	-	Ž	X	8-6-13 N=19			
				_	ķ	X	9-12-12 N=24	13		
6.0 C	LAYEY SAND WITH GRAVEL (SC) , light broense, moist.	own, medium dense	252+/- to	5 —	2	X	13-14-13 N=27	7		
				10-	Š	X	13-13-17 N=30	. 8		
				_						
				15-	2	X	23-22-20 N=42	9		
	ANDY SILT (ML) , with quartz fragments, broense, moist.	own, medium dense	239.5+/- to very	20	—	X	5-7-11 N=18	20		
00.5			2045.4							
23.5 S to	ILTY SAND (SM), with quartz fragments, gro o dense, moist.	eyish brown, medium	234.5+/- n dense	- 25-		X	9-14-23 N=37	21		
Stratif	ication lines are approximate. In-situ, the transition ma	ay be gradual.		Hamn	mer Ty	pe: A	utomatic			
Advancement HSA Abandonment Backfilled w		See Exhibit A-3 for desc procedures. See Appendix B for des procedures and addition See Appendix C for exp abbreviations.	cription of laboratory all data (if any).	Notes:	:					
	ATER LEVEL OBSERVATIONS			Boring S	Started	d: 6/14	1/2017	Boring Com	pleted: 6/14/2	017
✓ At cor	drilling mpletion of drilling	llerr	acon	Drill Rig				Driller: Reco	-	
After 2	24 hours	21505 Gre	enoak Way							



		BORING LO	OG NO. B-1	3				ſ	Page 2 of 4	4
PR	OJECT: Lubber Run Recreation Center	•	CLIENT: Bown 14020	nan () Thu	ons nde	sulti r Bo	ing olt Place S	uite 300		
SIT	E: 300 North Park Drive Arlington, Virginia									
00	LOCATION See Exhibit A-2			· ·	TEL ONS	'ΡΕ		(%	ATTERBERG LIMITS	
HICL	Latitude: 38.873156° Longitude: -77.114126°			DEPTH (Ft.)	Y LEV	E TY) TES ULTS	TER ENT (
GRAPHIC LOG		Approximate Sur	face Elev: 258 (Ft.) +/-	DEPI	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	LL-PL-PI	
	DEPTH	wich brown modium	ELEVATION (Ft.)		> 8	S,				
	<u>SILTY SAND (SM)</u> , with quartz fragments, great to dense, moist. <i>(continued)</i>	yish brown, mediun	rdense	_						
				_						
				_						
				_			9-14-23			
				20		X	N=37			
				30-						
				_						
	33.5 HIGHLY WEATHERED TO PARTIALLY WEAT	FUEDED SCUIST W	224.5+/-	_	\Box					
	quartz boulders, greyish brown, very dense, o	lry.	1001	_		X	35-50/6" N=50+	<u></u>		
				35-						
				_						
				_						
				-						
				_		M	15-47-50 N=97)		
				40-			11-97			
				_						
				_						
				_						
				_		\bigvee	35-41-50/	5"		
				45-		\triangle	N=50+			
				_						
				_						
				_						
				_	1256A	\geq	50/6"			
				50-			N=50+			
	Stratification lines are approximate. In-situ, the transition ma	y be gradual.			mer T	ype:	Automatic			
Advance	ement Method:	0 = 1 = 1 = 1		Notes	,.					
HSA		See Exhibit A-3 for desc procedures. See Appendix B for desc	•	Notes						
Ahand	onment Method:	procedures and addition See Appendix C for expl	al data (if any).							
Back	filled with Auger Cuttings	abbreviations.	and a symbolo did							
	WATER LEVEL OBSERVATIONS		5 6 24 44 4	Boring	Starte	d: 6/1	4/2017	Boring Com	pleted: 6/14/20	017
∇	While drilling At completion of drilling	llerr	acon	Drill Ri				Driller: Reco	-	
	After 24 hours Cave-in after 24 hours.	21505 Gred Dulle		Project	No.: I	<u>=W</u> 17	75052	Exhibit: A	4-12	

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17



EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17

GEO SMART LOG-NO WELL

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

BORING LOG NO. B-13 Page 3 of 4 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE **GRAPHIC LOG** WATER CONTENT (%) FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.873156° Longitude: -77.114126° LL-PL-PI Approximate Surface Elev: 258 (Ft.) +/-**ELEVATION (Ft.)** DEPTH HIGHLY WEATHERED TO PARTIALLY WEATHERED SCHIST (SP) with quartz boulders, greyish brown, very dense, dry. (continued) 50/0" N=50+ 55-50/0" N=50+ 60-50/0" N=50+ 193+/-65 QUARTZ BOULDER, white, very dense, RQD = 6.6%, dry. 191+/ HIGHLY WEATHERED TO PARTIALLY WEATHERED SCHIST, greyish N=50+ brown, very dense, RQD = 0%, dry. 70 N=50+ Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/14/2017 Boring Completed: 6/14/2017 While drilling At completion of drilling Drill Rig: CME-550/ ATV Driller: Recon Drilling After 24 hours 21505 Greenoak Way Cave-in after 24 hours Project No.: EW175052 A-4-12 Dulles, VA

BORING LOG NO. B-14 Page 1 of 2 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE **GRAPHIC LOG** WATER CONTENT (%) FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.873128° Longitude: -77.113727° LL-PL-PI Approximate Surface Elev: 260 (Ft.) +/-ELEVATION (Ft.) DEPTH 0.5 ASPHALT (6") 259.5+/-259.5+/-3-4-2 GRAVEL (2") N=6 FILL - SANDY LEAN CLAY, brown, medium stiff, moist. 5-7-7 256.5+/ N=14 CLAYEY SAND WITH GRAVEL (SC), light brown, medium dense, moist. 5 5-7-8 N=15 6-8-10 N=18 10 246.5+/-SILTY SAND WITH GRAVEL (SM), with gravel, light brown, dense to very 25-30-35 N=65 15 ∇ 6-10-15 N=25 **B** 20-8-14-14 N=28 25 Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/14/2017 Boring Completed: 6/14/2017 After 24 hours Drill Rig: CME-550/ ATV Driller: Recon Drilling 21505 Greenoak Way

Dulles, VA

Project No.: EW175052

A-4-13

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

Cave-in after 24 hours

GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17



			BORING LO	OG NO. B-1	14				ſ	Page 2 of	2
PI	ROJECT:	Lubber Run Recreation Center	er	CLIENT: Bowi	man (0 Thu	Cons	sulti r Bo	ing olt Place Su	ıite 300)	
SI	TE:	300 North Park Drive Arlington, Virginia									
GRAPHIC LOG		N See Exhibit A-2 8.873128° Longitude: -77.113727°	Approximate Sur	face Elev: 260 (Ft.) +/-	DЕРТН (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI	
000	DEPTH SILT dens	Y SAND WITH GRAVEL (SM), with grave, moist. (continued)	vel, light brown, dense	ELEVATION (Ft.) e to very		> 8 -	'S				
ACON_DATATEMPLATE.GDT 6/		ILY WEATHERED SCHIST , greyish bro	wn, very dense, dry.	226.5+/-	30 - - -	- - - -	X	20-30-50/5 N=50+			
GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17	SAN	DY SILT (ML) , trace mica, greyish brow	n, very dense, dry.		- 35- - - -	- - - -	X	15-20-25 N=45			
THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL EW175		ng Terminated at 40 Feet		220+/-	40-						
EPARAT		on lines are approximate. In-situ, the transition n	nay be gradual.				ype:	Automatic			
S Adva HS Abar Abar Ba	donment Met ckfilled with A	nod: nuger Cuttings	See Exhibit A-3 for desc procedures. See Appendix B for desi procedures and addition See Appendix C for exp abbreviations.	cription of laboratory nal data (if any).	Note	s:					
SING LO	WATE After 24 h	ER LEVEL OBSERVATIONS ours	There	acon	Boring	Starte	d: 6/1	4/2017 E	Boring Com	pleted: 6/14/2	017
IS BOF				enoak Way	Drill R	ig: CM	E-550)/ ATV	Oriller: Rec	on Drilling	
王 288	Cave-in a	fter 24 hours.	Dulle		Projec	t No.: E	EW 17	'5052	Exhibit: A	·-4-13	



BORING LOG NO. B-15 Page 1 of 2 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE WATER CONTENT (%) **GRAPHIC LOG** FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.872965° Longitude: -77.115069° LL-PL-PI Approximate Surface Elev: 262 (Ft.) +/-ELEVATION (Ft.) DEPTH 0.1_\TOPSOIL (1") /\262+*l*/ 6-8-10 SANDY LEAN CLAY WITH GRAVEL (CL), brown, very stiff, moist. N=18 259.5+/-GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17 CLAYEY SAND WITH GRAVEL (SC), reddish brown, medium dense, 4-7-7 N=14 257+/ 5 **LEAN CLAY WITH SAND (CL)**, reddish brown, very stiff, moist. 8-10-15 N=25 253.5+/ SANDY SILT (ML), light brown, medium dense, moist. 10-14-15 N=29 10 35-50/5" N=50+ 15 243.5+/-SANDY SILT WITH GRAVEL (ML), trace mica, light brown, stiff, moist. 7-10-14 N=24 20 THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. 8-10-15 N=25 25 Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/8/2017 Boring Completed: 6/8/2017 While drilling At completion of drilling Drill Rig: CME 550/AT V Driller: Recon Drilling After 24 hours 21505 Greenoak Way Project No.: EW175052 Cave-in after 24 hours Dulles, VA A-4-14



	BOR	RING LO	G NO. B-1	5					Page 2 of 2	2
PR	OJECT: Lubber Run Recreation Center		CLIENT: Bowr	nan (Cons	ulti	ing olt Place Su	uite 300	1	
SIT	ΓΕ: 300 North Park Drive Arlington, Virginia		1-1020	, i i i u	iido:		71. T 1400 O	ante 000		
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.872965° Longitude: -77.115069°	Approximate Surf	face Elev: 262 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS	
	DEPTH SANDY SILT WITH GRAVEL (ML), trace mica, light (continued)	brown, stiff, m	ELEVATION (Ft.)		-0	S				
	28.5 HIGHLY WEATHERED SCHIST, greyish brown, very	y dense, moist	. 233.5+/-	30-	₩		25-35-50/3	"		
	33.5 SANDY SILT (ML), trace mica, greyish brown, very	dense, moist.	228.5+/-	35 - -		X	35-28-25 N=53			
	40.0 Paring Terminated at 40 Foot		222+/-	- - 40-		X	16-30-27 N=57			
	Boring Terminated at 40 Feet									
	Stratification lines are approximate. In-situ, the transition may be gra	adual.		Ham	mer Ty	/pe:	Automatic		· · · · · · · · · · · · · · · · · · ·	
HSA Abando	proced See Approced Ionment Method:	opendix B for desc lures and additiona	ription of laboratory	Notes	S:					
∇	WATER LEVEL OBSERVATIONS While drilling	L		Boring	Starte	d: 6/8	3/2017	Boring Com	pleted: 6/8/201	17
<u>V</u>	At completion of drilling After 24 hours	21505 Gree	OCON	Drill Ri	g: CME	550	/AT V	Driller: Rec	on Drilling	
129	Cave-in after 24 hours.	21505 Gree Dulles		Project	No.: E	W17	5052	Exhibit: A	·-4-14	

BORING LOG NO. B-16 Page 1 of 2 **PROJECT: Lubber Run Recreation Center CLIENT: Bowman Consulting** 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE **GRAPHIC LOG** WATER CONTENT (%) FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.872832° Longitude: -77.11421° LL-PL-PI Approximate Surface Elev: 260 (Ft.) +/-ELEVATION (Ft.) **DEPTH** 0.5 ASPHALT 6") 0.7 SANDY LEAN CLAY WITH GRAVEL (CL), brown, very stiff, moist. 259.5+/-/259.5+/-10-11-7 N=18 POORLY GRADED GRAVEL (GP), Gravel (2") 257.5+/-CLAYEY SAND WITH GRAVEL (SC), reddish brown, medium dense, GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 7/5/17 3-3-4 N=7 5 **LEAN CLAY WITH SAND (CL)**, reddish brown, very stiff, moist. 3-5-4 N=9 251.5+/-SANDY SILT (ML), light brown, medium dense, moist. 10-18-22 N=40 10 30-50/6" N=50+ 10-14-18 N=32 20 14-14-20 N=34 25 Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/8/2017 Boring Completed: 6/8/2017 After 24 hours Drill Rig: CME 550/AT V Driller: Recon Drilling 21505 Greenoak Way Project No.: EW175052 Exhibit: A-4-15 Cave-in after 24 hours Dulles, VA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.



Г			BORING LO	OG NO. B-1	16					Page 2 of	2
PR	OJECT:	Lubber Run Recreation Cen	ter	CLIENT: Bowr	nan (Cons	sult r Ra	ing olt Place S	uite 300)	
SI	ΓE:	300 North Park Drive Arlington, Virginia		17020	J 111G	ii i a c				,	
GRAPHIC LOG	Latitude: 38	N See Exhibit A-2 3.872832° Longitude: -77.11421°	Approximate Sui	face Elev: 260 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	LL-PL-PI	
	33.5 HIGH	DY SILT (ML), light brown, medium d		226.5+/-	30-			14-22-30 N=52 18-30-50/5 50/4" N=50+			
Advar HS.	ncement Meth A donment Meth ckfilled with A		See Exhibit A-3 for desc procedures. See Appendix B for des procedures and addition	cription of laboratory	Note	s:		Automatic			
$\overline{\nabla}$	After 24 h		Tierra	əcon	Boring Drill R				Boring Com Driller: Rec	on Drilling	17
	Cave-in a	fter 24 hours.	21505 Gre	enoak Way es, VA	Projec	t No.: E	EW 17	75052	Exhibit: A	\-4-15	



"		BORING LO	OG NO. B-1	17				F	Page 1 of 2
PR	OJECT: Lubber Run Recreation Cente	r	CLIENT: Bowi	man C	onsi	ulting	g Blace S:		<u> </u>
SI	E: 300 North Park Drive Arlington, Virginia		14020	U I NU	naer	BOIL	Place St	lite 300	
GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude: 38.872799° Longitude: -77.113807°	Approximate Sur	face Elev: 262 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI
	DEPTH 0.1 \(\triangle TOPSOIL \)(1") FILL - SANDY SILT WITH GRAVEL (ML), bro	own, very stiff, moist.	ELEVATION (Ft.) /\262+I/	_		\downarrow	4-4-13 N=17		
DT 6/24/17	2.5 SILTY, CLAYEY SAND (SC-SM), reddish bro	wn, medium dense, ı	259.5+/- moist.	_		X	6-9-7 N=16		
4TAIEMPLAIE.G				5 — –	2		6-8-8 N=16		
CREA.GPJ LERRACION_DV				10-	2		5-6-8 N=14	12	24-19-5
NO WELL EWITSOSZ LUBBER RUN RECKEA GPJ TERRACON DATA IEMPLATE, GDT 6/24/17	13.5 SILTY SAND WITH GRAVEL (SM), yellowish	brown, very dense, r	248.5+/- moist.	- - 15-			30-50/4" N=50+		
GEO SMARI LOG-				- - 20-			40-50/3" N=50+		
Advard HS. Advard HS. Advard HS. Advard HS.	23.5 SILTY CLAY (CL/ML), light brown, hard to ve	ery hard, moist.	238.5+/-	- - 25-	\ 		14-18-20 N=38		
AKAIE	Stratification lines are approximate. In-situ, the transition management	ay be gradual.		Ham	mer Ty	oe: Aut	tomatic	l	
Advar HS. Abanc Bac	cement Method: A onment Method: kfilled with Auger Cuttings	See Exhibit A-3 for desc procedures. See Appendix B for des procedures and addition See Appendix C for exp abbreviations.	cription of laboratory al data (if any).	Notes	i:				
	WATER LEVEL OBSERVATIONS After 24 hours	75		Boring	Started	: 6/8/20)17	Boring Com	oleted: 6/8/2017
S BOK		21505 Gre	enoak Way	Drill Rig				Driller: Reco	-
T 1888	Cave-in after 24 hours.		s, VA	Project	No.: E	N1750	52	Exhibit: A	-4-16



PROJEC	T: Lubber Run Recreation Co	BORING LO	CLIENT: Bow		Cons	ıılti	na		Page 2 of	
PROJEC	1. Lubber Kull Recreation Co		1402	0 Thu	ınde	r Bo	olt Place S	uite 300)	
SITE:	300 North Park Drive Arlington, Virginia									
LOCATO Latitude	TION See Exhibit A-2			·:	/EL ONS	TYPE	<u> </u>	(%)	ATTERBERG LIMITS	
Latitude	: 38.872799° Longitude: -77.113807°			DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	ET.	FIELD TEST RESULTS	WATER CONTENT (%)		
<u> </u>		Approximate Su	rface Elev: 262 (Ft.) +/-	DEPI	ATE 3SER	SAMPLE	PELI	M NO	LL-PL-PI	
DEPTH	LTV OLAY (OL/MI) Cabb bassar bassar		ELEVATION (Ft.)		> 8	Ś		0		
<u> 21</u>	LTY CLAY (CL/ML), light brown, hard	to very nard, moist. (cont	inuea)	_	1235A					
				_	162343					
							11.00.10			\vdash
				_		X	14-28-40 N=68			
				30-						Г
				-						
				-						
33.5			228.5+/-	_						
<u>EI</u>	_ASTIC SILT (MH), greyish brown, ver	y hard, moist.		_		\bigvee	21-31-45 N=70			
				35-		\triangle	N=76			_
				_						
				_						
				_						
38.5 S	ANDY SILT (ML), trace mica, greyish I	prown, very hard, moist.	223.5+/-							
40.0		•	222+/-	40						
	oring Terminated at 40 Feet			40–						
Stratifi	cation lines are approximate. In-situ, the transi	ion may be gradual.		Han	nmer Ty	ype: /	Automatic			L
vancement N HSA	Method:	See Exhibit A-3 for desc procedures.	cription of field	Note	s:					
		See Appendix B for des procedures and addition								
andonment I Backfilled wi	Method: th Auger Cuttings	See Appendix C for exp abbreviations.	lanation of symbols and							
				_						
	ATER LEVEL OBSERVATIONS 24 hours	166	acon	Boring	Starte	d: 6/8	/2017	Boring Com	pleted: 6/8/20	17
		•		Drill R	ig: CMI	E 550	/AT V	Driller: Rec	on Drilling	
Cave-	in after 24 hours.		enoak Way es, VA	Projec	t No.: E	W17	5052	Exhibit: A	N-4-16	

PROJECT	: Lubber Run Recreation Cer	nter	CLIENT: Bowi	man (Cons	ulti	ng _		
SITE:	300 North Park Drive Arlington, Virginia		1402	0 Thu	nde	r Bo	lt Place S	uite 300	
CAPHIC LO	ON See Exhibit A-2 8.872605° Longitude: -77.114254°	Approximate Sur	face Elev: 260 (Ft.) +/-	DEРТН (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLETYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS LL-PL-PI
0.7 POC	PHALT (6") DRLY GRADED GRAVEL (GP), GRAV LYEY SAND (SC), with gravel, reddish st.		ELEVATION (Ft.) 259.5+/- 259.5+/- to dense,		-	X	6-12-13 N=25		
				- -	-	X	7-10-10 N=20		
6.0 SIL1 brov	TY SAND WITH QUARTZ FRAGMENT vn, very dense, moist.	「 <u>S (SM)</u> , trace clay, yello		5 - -		X	14-21-32 N=53		
				- 10-		X	30-30-43 N=73	:	
				- - 15-		X	44-50/6" N=50+		
18.5 SIL1	ΓΥ SAND (SM) , trace mica, greyish br	rown, hard, moist.	241.5+/-	- - 20- -			10-14-16 N=30	:	
25.0	tion lines are approximate. In-situ, the transitic	on may be gradual	235+/-	25-	mer T	Whe: A	14-16-22 N=38 Automatic	!	
dvancement Me HSA bandonment Me Backfilled with	thod:	See Exhibit A-3 for desc procedures. See Appendix B for des procedures and additior See Appendix C for exp abbreviations.	cription of laboratory nal data (if any).	Notes		, μσ. <i>F</i>	econdit.		
WAT ✓ After 24	ER LEVEL OBSERVATIONS hours	Tecc	əcon	Boring					pleted: 6/9/20
				Drill Ri	ig: CM	E 550/	AT V	Driller: Reco	on Drilling



	BORI	ING LO	G NO. I	B-19	9				I	Page 1 of 2
PRC	OJECT: Lubber Run Recreation Center		CLIENT: B	30wm 4020	an C Thu	ons nder	ultir Bol	ng It Place Si	uite 300	
SITE	E: 300 North Park Drive Arlington, Virginia									
GRAPHICLO	LOCATION See Exhibit A-2 Latitude: 38.872554° Longitude: -77.113833° Appert	pproximate Surfa	ace Elev: 262 (Ft. ELEVATION		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	ATTERBERG LIMITS
	L2_\TOPSOIL (2") FILL - SANDY SILT (ML), with gravel brick fragments,	, brown, stiff,		262+/			X	4-6-7 N=13		
2	CLAYEY SAND WITH GRAVEL (SC), reddish brown, dense, moist.	dense to med		9.5+/-	_	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		10-15-20 N=35		
					5 —	2		13-16-20 N=36		
					- 10-			8-9-8 N=17		
110	3.5 SILTY SAND WITH GRAVEL (SM), trace clay, brown,	, very dense, r		8.5+/-	_	1999		22-40-44 N=84		
					15— — —	4		N-04		
					- 20- - -			50/6" N=50+		
	25.0		2	237+/-	- 25-			14-19-18 N=37	19	46-34-12
	Stratification lines are approximate. In-situ, the transition may be grade	lual.		·	Ham	mer Ty	pe: A	utomatic	,	,
HSA pandor	procedure See Appe procedure	endix B for descr res and additiona endix C for expla	iption of laborato I data (if any).	·	Notes	s :				
	WATER LEVEL OBSERVATIONS				Boring	Started	· 6/0/	2017	Boring Com	pleted: 6/9/201
	Groundwater not encountered	erra	ocor			g: CME			Driller: Rec	-
	Cave-in after 24 hours.	21505 Greer Dulles,	noak Way	· - }		: No.: E			Exhibit: A	





BORING LOG NO. INF-1 Page 1 of 1 **PROJECT: Lubber Run Recreation Center** CLIENT: Bowman Consulting 14020 Thunder Bolt Place Suite 300 SITE: 300 North Park Drive Arlington, Virginia ATTERBERG LIMITS WATER LEVEL OBSERVATIONS LOCATION See Exhibit A-2 SAMPLE TYPE WATER CONTENT (%) **GRAPHIC LOG** FIELD TEST RESULTS DEPTH (Ft.) Latitude: 38.873211° Longitude: -77.115228° LL-PL-PI Approximate Surface Elev: 260 (Ft.) +/-DEPTH **ELEVATION (Ft.)** \$0.2_\TOPSOIL (2") ^260+/₂ 4-6-6 12 FILL - CLAYEY SAND WITH GRAVEL, brown, medium dense, moist. N = 12257.5+/-GEO SMART LOG-NO WELL EW175052 LUBBER RUN RECREA.GPJ TERRACON_DATATEMPLATE.GDT 6/24/17 FILL - SANDY SILT WITH GRAVEL, trace clay, light brown, stiff, moist. 3-8-7 16 N=15 255+/ 5 SILTY SAND (SM), with quartz fragments, light brown, medium dense to 5-8-15 19 very dense, moist. N=23 30-40-45 6 N=85 10 20-22-30-35 N=52 13-25-35-25 **1999** N=60 22-17-18-20 15 16 38-34-4 244.5+/-N = 35SANDY SILT (ML), greyish brown, very stiff, moist. 7-10-12 N=22 5-10-14 N=24 241+/-Boring Terminated at 19 Feet Stratification lines are approximate. In-situ, the transition may be gradual. Hammer Type: Automatic Advancement Method: Notes: See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any). See Appendix C for explanation of symbols and Abandonment Method: Backfilled with Auger Cuttings WATER LEVEL OBSERVATIONS Boring Started: 6/14/2017 Boring Completed: 6/14/2017 Groundwater not encountered Drill Rig: CME-550/ ATV Driller: Recon Drilling

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

Cave-in after 24 hours

21505 Greenoak Way Project No.: EW175052 Exhibit: Dulles, VA A-4-19







APPENDIX B LABORATORY TESTING



Lubber Run Recreation Center ■ Arlington, Virginia June 23, 2017 ■ Terracon Project No. EW175052



Laboratory Testing

The boring logs and samples were reviewed by a geotechnical engineer who selected soil samples for testing. Tests were performed by technicians working under the direction of the engineer. A brief description of the tests performed follows.

Particle size analysis, liquid and plastic limit tests, moisture content measurements and unit weight tests were made to aid in classifying the soils in accordance with the Unified Soil Classification System (USCS). The USCS is summarized in Appendix C.


Test procedures may have been modified to reflect local practices or conditions.

The results of the laboratory tests are presented in Appendix B.



GRAIN SIZE DISTRIBUTION

ASTM D422



21505 Greenoak Way Dulles, VA


EXHIBIT: B-1

ABORATORY.

DRAFT

GRAIN SIZE DISTRIBUTION

ASTM D422




Dulles, VA

EXHIBIT: B-2




ATTERBERG LIMITS RESULTS

ASTM D4318



Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines		
/0 TJ	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay	
0.0	0.0	0.0	1.5	11.8	53.2	30.6	2.9	

SIEVE	PERCENT	SPEC.*	PASS?
SIZE	FINER	PERCENT	(X=NO)
#4	100.0		
#10	98.5		
#16	98.3		
#30	93.7		
#40	86.7		
#50	77.8		
#60	72.2		
#100	53.9		
#200	33.5		
#270	29.4		
0.0345 mm.	22.9		
0.0225 mm.	15.3		
0.0132 mm.	10.2		
0.0094 mm.	7.7		
0.0067 mm.	5.1		
0.0048 mm.	2.6		
0.0034 mm.	0.0		
0.0024 mm.	0.0		
0.0014 mm.	0.0		
0.0010 mm.	0.0		

	Soil Description	
Brown, Silty san	d	
PL= 34	Atterberg Limits LL= 38	PI= 4
D ₉₀ = 0.4921 D ₅₀ = 0.1348 D ₁₀ = 0.0129	Coefficients D ₈₅ = 0.3954 D ₃₀ = 0.0559 C _u = 13.76	D ₆₀ = 0.1770 D ₁₅ = 0.0220 C _c = 1.37
USCS= SM	Classification AASHT	O= A-2-4(0)
	<u>Remarks</u>	

(no specification provided)

Location: INF-1 **Sample Number:** S-7 **Date:** 06-23-17 **Depth:** 14.0 - 16.0'

Geotechnical Consulting & Testing, Inc. a Terracon Company

Dulles, VA

Client: Bowman Consulting


Project: Lubber Run Recreation Center

Project No: EW175052

Figure

DRAFT

LIQUID AND PLASTIC LIMITS TEST REPORT



	SOIL DATA								
SYMBOL	SOURCE	SAMPLE NO.	DEPTH	NATURAL WATER CONTENT (%)	PLASTIC LIMIT (%)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USCS	
•	INF-1	S-7	14.0 - 16.0'	15.6	34	38	4	SM	

Geotechnical Consulting & Testing, Inc.
a Terracon Company
Dulles, VA


Client: Bowman Consulting

Project: Lubber Run Recreation Center

Project No.: EW175052

Figure





	SOIL DATA									
T	Source	Classifi4i-								
	Source	Sample Depth No.		Sand	Silt	Clay	Classification			
0	INF-1	S-7	14.0 - 16.0'	70.2	29.8	0.0	Loamy sand			
-										
-										
-										
-										
_										
						1				
\perp										

Geotechnical Consulting & Testing, Inc.
a Terracon Company
Dulles, VA

Client: Bowman Consulting

Project: Lubber Run Recreation Center

Project No.: EW175052

Figure